



22nd OCT 2025

Dear Sirs,

QUOTATION NO: Q/PB/159/R1/2025.

You are invited to submit your quotation for carrying out the following works.

Supply and Installation of Chilled Water Pipes at Serendib Lounge, Terminal Building, Airport, Katunayake.

1. Please ensure that the **e-mail as subject** is clearly entered **Q/PB/159/R1/2025 Supply and Installation of Chilled Water Pipes at Serendib Lounge, Terminal Building, Airport, Katunayake.** For easy identification of your quote. The quotation must be submitted by an email to ulpropbids@srilankan.com not later than **10:00 hrs on 11/11/2025.** [Refer clause 08 of instructions to bidders for clarifications.]
2. Any quotation received after the quotation closing time and date will not be considered. Please note that your quotation shall remain, depend on the job.
3. All quotations should be prepared in accordance with written instructions, the specifications, drawings or samples of SriLankan Airlines Limited.
4. Any failure to comply with written instructions, the specifications, drawings or samples of SriLankan Airlines may result in the quotation being rejected.
5. Any inquiry regarding inspection of worksite or the specifications of the work could be referred to Telephone **No. 074 444 2883 Mr. Sumith Appuhamy** Further instructions to be followed are available with this letter as instructions to bidders.
6. SriLankan Airlines Limited shall not be bound to accept whole, the lowest or any quotations. SriLankan Airlines also reserved the right to accept any quotation in part if it so desires.
7. The employer shall make advance payment to the contractor **(if required)** in an amount equivalent to 30% of the initial contract price excluding provisional sums and contingencies, after furnishing of an unconditional guarantee accordance with CIDA format by a bank to the employer. The guarantee shall remain effective until the advance payment has been repaid, but the amount of the guarantee shall be progressively reduced by the amounts repaid by the contractor. Interest will not be charged on the advance payment and bidder should bear the cost for the guarantee.

Yours faithfully,

SRILANKAN AIRLINES LIMITED
Sumith Appuhamy
Facilities Manager (Mechanical)

SriLankan Airlines Ltd.
Air Line Centre, Bandaranaike International Airport,
Katunayake



INSTRUCTIONS TO BIDDERS

01. The contractor bidding shall be satisfied with the information provided in the BOQ and drawings provided. If required contractor could visit the site and inspect the work to be done. Also if required could send an e-mail and obtain any missing information.
02. The contractor shall quote, meeting specifications with the intension of delivering a quality job. For any extra work items (outside items specified in BOQ) approval of rates shall be obtained in writing prior to commencement of extra works. Failing same adjustments to rates will be done without consultation.
03. Since SriLankan premises is a security restricted area you may have to be ready with Police reports, Gramasevaka reports certified by AGA and two photographs to obtain entry passes for workman and drivers when submitting quotations for the job.
04. The equipment, fittings and fixtures supplied shall have minimum one year warranty unless otherwise specifically stated in the BOQ which will overrule.
05. Retention amount will be 2.5% of certified bill value for jobs up to 1.0 million and 5% for above 1.0 million. Retention period is six months. (50% of foreign component paid directly to third parties will be considered in calculating retention sum)
06. Duty free facility is available for items (excluding items restricted by the BOI) required to accomplish the project. Please do not quote SSCL, VAT & PAL for foreign component, if consignee in CUSDEC is SriLankan Airlines Limited.
07. The contractor shall make every endeavour to keep the working premises clean and tidy. Within two weeks after practical completion, debris and balance material shall be removed from the site. Any materials or saleable debris belongs to SriLankan Airlines Ltd shall be transferred to the SriLankan dumping yard. Please built in the above said cleaning, clearing and transfer cost to the BOQ if not specifically requested. In the event failure to remove balance material and debris within two weeks after completion of works cost of removal and penalty will be charged.
08. Please note that you could submit the offers on or before quotation closing time and date by email to secure email address ulpropbids@srilankan.com.
09. Time for completion period is **03 weeks** & Amount of Liquidated damages 0.05% of contract value per day.

BILL OF QUANTITIES

TYPE OF WORK : Supply and Installation of Chilled Water Pipes.

QUOTATION NO :Q/PB/159/R1/2025

LOCATION : Serendib Lounge, Terminal Building, Airport, Katunayake.

ITEM	QTY	UNIT	DESCRIPTION	RATE	AMOUNT
01	Item		Close the valve and Cut the existing SS chilled water pipe, supply and weld of SS two nos of T connections 10"x2.5". Supply and installation of 4 ft lengths of 2 ½ " inch internal diameter SS pipe. This work is required to complete within 5 hours duration and two well qualified welders are required. Insulation 2" thick foam closed cell polyethylene pipe insulation. All valves, fittings and flanges shall be insulated Wrap bend joints/pressured joints with closed cell insulation tape of 50mm wide to the same standard and connected. All pipe insulation should be with a factory laminated aluminium jacket not less than 0.9mm thickness.		
02	04	Nos	Suply and Installation of 2 ½ " internal diameter Gate valve, Flanged type, fully stainless steel, PN-16 working pressure, hand wheel type, heavy duty, (Made in Singapore, Korea, Taiwan, and Thailand or substantially equal) Valve is required to insulate with 2" thick foam closed cell polyethylene pipe insulation with a factory laminated aluminium jacket not less than 0.9mm thickness.		

ITEM	QTY	UNIT	DESCRIPTION	RATE	AMOUNT
03	360	FT	Supply and Installation of 2 ½" inch internal diameter, BI pipe schedule 40 according to ASTM A53, with 2" thick foam closed cell polyethylene pipe insulation. All valves, fittings and flanges shall be insulated Wrap bend joints/pressured joints with closed cell insulation tape of 50mm wide to the same standard and connected. All pipe insulation should be with a factory laminated aluminium jacket not less than 0.9mm thickness. Roof supports shall be as per attached drawing. Inside building supports 3"x2" x 3mm C Chanel with 15mm threaded anchor rods to the slab in every 6ft distance.		
04	Item		Do the pressure test for 240 Psi. keep one day. Include cost for any pipe modification for the pressure testing. Note: (1) One year warranty period is required for the above installation work. 2) Separate portable Diesel Generator is required for the welding work. (3) Police reports are required to obtain permanent AASL Passes. (4) Continuous working may be not allowed to due to passenger busy schedule. You may want to adjust the work accordingly. SSCL : VAT: TOTAL: NAME OF THE COMPANY: SIGNATURE: DATE: The successful bidder and his employees will be required to submit the following documents in order to obtain passes to enter SriLankan Airlines Premises. * Police Clearance Certificate. * Gramasevaka Certificate.		

ITEM	QTY	UNIT	DESCRIPTION	RATE	AMOUNT
			* National Identity Card. * Recently taken Passport size Photograph. * Certified by Gramasevaka. * Stamp size photograph		